



**WINWOOD POND
DREDGING PROJECT**
TOWN OF ADDISON
DALLAS COUNTY, TEXAS



HALFF
12225 GREENVILLE AVE., SUITE 200
DALLAS, TEXAS 75243
TEL: 972.980.8200
FAX: 972.980.8202

| Revision No. | Date | Description |
|--------------|------|-------------|
| | | |
| | | |
| | | |
| | | |



The seal appearing on this document was authorized by Timothy E. Lackey, PE #61212 on 04-28-16. Absorption of a sealed document without proper notification to the responsible engineer is an offense under the Texas Engineering Practice Act. The record copy of this drawing is on file at the office of Halff Associates, Inc. 12225 Greenville Avenue, Suite 200, Dallas, Texas 75243. TBPE #PM #P-312.

Project No.: 29751-WA21
Issued: 4/28/2016
Drawn By: HC
Checked By: TL
Scale: AS NOTED

Sheet Title
PROJECT LAYOUT
C1.01
Sheet Number

- LEGEND**
- LIMITS OF CONSTRUCTION
 - CONSTRUCTION ROAD

- Notes:**
1. The Contractor shall contact the Town of Addison Infrastructure Operations and Services Department prior to any sign removal. Sign removal and reinstallation/relocation shall be in good condition equal to or better than existing condition, and as per the Engineers specifications with the cost incidental to the Project Bid Items.
 2. All fences, signs, and property corner monuments removed for, or damaged during construction shall be replaced or repaired to as good a condition or with a better material than the existing as per the Engineer's specifications. Extra payment shall not be made for this work.
 3. The Contractor shall be responsible for taking all precautions to protect existing trees except on specific authority of the Engineer.
 4. The Contractor shall be responsible for taking all precautions to protect existing inlets and fountains.
 5. The Contractor shall be responsible for repairing any damage caused by the Contractor outside of the designated work area with equal or better quality material at the Contractor's expense.
 6. Refer to General Notes for sprinkler system.
 7. Construction vehicles and material are not allowed in parking lots and streets outside the project limits or within private property.
 8. The Contractor shall take reasonable measures to avoid unnecessary noise.