



3010 Gaylord Parkway
Suite 190
Frisco, TX 75034
TEL 972.377.7480
FAX 972.377.8380
www.GarverUSA.com

DATE: February 12, 2020

TO: Joel Jenkinson, AAE
Airport Director
Addison Airport
16051 Addison Road
Suite 220
Addison, TX 75001

PROJECT: Addison Airport
Work Order No. 1
Fuel Farm Exit Relocation and Perimeter Road Repairs

Garver has reviewed the proposed changes to the contract and recommend proceeding as indicated below and attached to this letter.

DESCRIPTION OF CHANGES TO THE CONTRACT:

Change Order No. 2, dated 2020-02-11:

- **New items to be added to the contract in Base Bid B:**
 - SS-350-5.2 "George Haddaway Gate Relocation" will be added to Base Bid B for the addition of the relocation of the George Haddaway gate in preparation for the Galaxy FBO construction project.
- **Additional Contract time:**
 - 50 additional calendars days have been added to the completion date to complete the work associated with the addition of the George Haddaway Gate Relocaiton.

Revisions to Contract Amount

1) Original Contract Sum	\$	633,907.11
2) Net Changes by previously approved Change Orders	\$	29,815.00
3) Current Contract Amount (1+2)	\$	663,722.11
4) Total Change Order No. 002	\$	28,200.00
5) New Contract Sum (3+4)	\$	691,922.11
6) Total Increase/Decrease to Contract Amount		+9.09%

CHANGE ORDER NO. 2

Revisions to Contract Time

1) Contract Time Change

a. Original Contract Start Date	September 30, 2019
b. Original Contract Time	90 Calendar Days
c. Previously Approved Changes	0 Calendar Days
d. Additional Contract Time This Change Order	50 Calendar Days
e. New Contract Time (b+c+d)	140 Calendar Days
f. New Contract Completion Date (a+e)	February 17, 2020

Signature/Date:



Digitally Signed 02/12/2020

Sara Andrews, P.E.
Project Manager

Attachments: Construction Contract Change Order No. 2



3010 Gaylord Parkway
Suite 190
Frisco, TX 75034
TEL 972.377.7480
FAX 972.377.8380
www.GarverUSA.com

CELEBRATING
ONE HUNDRED YEARS
1919 to 2019



Construction Contract Change Order

Project: Fuel Farm Exit Relocation and Perimeter Road Repairs Addison Airport Garver Job No. 19A11000	Change Order No. 2
Owner: Town of Addison 5300 Belt Line Road Addison, Texas 75254	Date Prepared: 2/11/2020 Prepared by: Sara Andrews, PE
Contractor: Nu-Way Construction, LLC PO Box 270416 Flower Mound, Texas 75027	

Description of Work Included in Contract

The project consists of the three main project types. Base Bid A consists of the relocation of the existing fuel tanker transport truck exit for the fuel farm off George Haddow Drive and Addison Road. Base Bid B consists of the realignment of 800 linear feet of the airport perimeter road at the south end of the airfield starting at Taxiway Q. Base Bid C and additive alternates are for various concrete pavement repairs on airport perimeter road, aprons and taxiways.

Changes and Reasons Ordered (List Individual Changes as: A, B, C, D, etc.)

A Relocation of the George Haddaway gate

Attachments: Plans and specifications

Contract Changes	Bid Item No.	Bid Item Description	Unit of Measure	Estimated Quantity	Unit Price	Revised Estimated Cost
------------------	--------------	----------------------	-----------------	--------------------	------------	------------------------

PERIMETER ROAD RELOCATION (BASE BID B)

NEW PAY ITEMS

A	SS-350-5.2	GEORGE HADDAWAY GATE RELOCATION	L.S.	1.00	\$28,200.00	\$28,200.00
---	------------	---------------------------------	------	------	-------------	-------------

Base Bid B Subtotal \$28,200.00

(Base Bid B) Summation of Cost \$28,200.00


Estimated Project Cost		Time Change	
	Estimated Project Cost		
Original Contract Amount	\$633,907.11	Original Contract Start Date	9/30/2019
Previously Approved Changes	\$29,815.00	Previously Approved Changes (Calendar Days)	0
This Change Order	\$28,200.00	Original Total Contract Time (calendar days)	90
New Contract Amount	\$691,922.11	Additional Contract Time This Change Order (Calendar Days)	50
		New Contract Completion Date	2/17/2020

THIS AGREEMENT IS SUBJECT TO ALL ORIGINAL CONTRACT PROVISIONS AND PREVIOUS CHANGE ORDERS

ISSUED FOR REASONS

INDICATED ABOVE

Engineer: Garver


Engineer's Signature

Project Manager


02/12/2020

Title

Date

ACCEPTED BY
CONTRACTOR


Contractor's Signature


Title

2-11-2020
Date

APPROVED BY
OWNER

Owner's Signature

Title

Date



WOMAN OWNED

SMALL BUSINESS

January 13, 2020

Ms Sara Andrews
Garver Engineering
Addison Airport

RE: Existing Gate Relocation Proposal:

Gate proposal is for gate installation, concrete work, and electrical connection per Gate Layout Drawing, EX 101. This bid is for a fully functional existing gate with existing keypad and operator.

- Existing 26' sliding gate
 - Modify existing gate as needed to work with existing operator
 - Relocate Keypad
 - Loops per drawing
 - Posts as needed
 - \$12,500.00
- Concrete Pavement 10" 4,500 PSI
 - Asphalt removal
 - Approx 45 SY of 10" flexbase (tx247) under new pavement (area is too small for lime)
 - Approx 45 SY of 10" Concrete Pavement
 - Install concrete for controller and keypad
 - Total \$ 9,500.00
- Electrical Power source
 - Install electrical conduit adjacent to existing fuel shutoff conduit
 - Connect power source for Operator to existing electrical cabinet located approx. 75 lf from controller.
 - Connect power to operator box
 - Total \$6,200.00

Total \$28,200.00