



PRELIMINARY EVALUATION AND ASSESSMENT REPORT

Celestial 6.0 MG Ground Storage Tank
5510 Celestial Road
Addison, Texas

Project 00138755.000A
August 25, 2014



August 25, 2014
Project 00138755.000A

Ms. Lisa Pyles
Director Infrastructure Operations and Services
Town of Addison
16801 Westgrove Drive
Addison, Texas 75001

**Reference: PRELIMINARY EVALUATION AND ASSESSMENT REPORT
Celestial Ground Storage Tank**

Dear Ms. Pyles:

Kleinfelder has completed the authorized site visit and Preliminary Evaluation and Assessment Report for the Celestial Concrete Ground Storage Tank (GST) located at 5510 Celestial Road, Addison, Texas.

The purpose of this report is to describe the procedures that were undertaken to complete the evaluation and assessment, to record observations, and to present the resulting replacement and rehabilitation (R&R) recommendations of Town of Addison's 6 million gallon (MG) Celestial Ground Storage Tank (GST).

We appreciate the opportunity to provide our services for this project and look forward to the design phase.

Sincerely,

KLEINFELDER CENTRAL, INC.
Texas Registered Engineering Firm F-5592

A handwritten signature in black ink that reads "C.P. Nawal". The signature is fluid and cursive.

C.P. Nawal, PE
Project Engineer

A handwritten signature in blue ink that reads "Freddie Guerra". The signature is stylized and cursive.

Freddie Guerra, RS CAPM
Project Manager

A Report Prepared for:

Town of Addison
Addison, Texas

CELESTIAL 6.0 MG GROUND STORAGE TANK
5510 Celestial Road
Addison, Texas

Project 00138755.000A
August 25, 2014

Prepared by:



C.P. Nawal, PE
Project Engineer



Freddie Guerra, RS CAPM
Project Manager



7805 Mesquite Bend Dr., Suite 100
Irving, Texas 75063
p | 972.868.5900
f | 972.409.0008
Texas Registered Engineering Firm F-5592

This document was prepared for use only by the client, only for the purposes stated, and within a reasonable time from issuance, but in no event later than one year from the date of the report. Non-commercial, educational, and scientific use of this report by regulatory agencies is regarded as a "fair use" and not a violation of copyright. Regulatory agencies may make additional copies of this document for internal use. Copies may also be made available to the public as required by law. The reprint must acknowledge the copyright and indicate that permission to reprint has been received.

TABLE OF CONTENTS

	PAGE
EXECUTIVE SUMMARY	V
1 PURPOSE.....	1
2 BACKGROUND.....	2
3 EXISTING FACILITY INFORMATION.....	3
4 PROJECT APPROACH.....	4
4.1 DEFINITIONS.....	5
5 EVALUATIONS AND ASSESSMENT RESULTS	7
5.1 COATING SYSTEM	8
5.1.1 Exterior	8
5.1.2 Interior	9
5.2 STRUCTURAL	9
5.2.1 Exterior & Appurtenances.....	10
5.2.2 Interior & Appurtenances.....	10
5.2.3 Foundation.....	10
5.3 SAFETY & SECURITY	11
5.3.1 Ladders.....	11
5.3.2 Roof Hatch.....	11
5.3.3 Fencing & Gate.....	12
5.4 OPERATIONAL.....	12
5.4.1 Inlet Pipe & Valves.....	12
5.4.2 Outlet Pipe & Valve.....	12
5.4.3 Overflow Pipe, Weir & Catchment	12
5.4.4 Level Indicator	13
5.4.5 Vents	13
5.4.6 Lighting.....	13
5.4.7 Instrument & Control Systems	13
5.5 SANITARY	14
5.5.1 Roof Hatch.....	14
5.5.2 Roof Vent.....	14
5.5.3 Overflow.....	14
6 CONCLUSIONS AND RECOMMENDATIONS	15
6.1 COATING SYSTEM	15
6.1.1 Exterior	15
6.1.2 Interior	15
6.2 STRUCTURAL	16
6.2.1 Exterior & Appurtenances.....	16
6.2.2 Interior & Appurtenances.....	16
6.2.3 Foundation.....	17
6.3 SAFETY & SECURITY	17
6.3.1 Ladders.....	17
6.3.2 Roof Hatch.....	17
6.3.3 Fencing & Gate.....	17

TABLE OF CONTENTS (continued)

	PAGE
6.4 OPERATIONAL	17
6.4.1 Inlet Pipe & Valves.....	17
6.4.2 Overflow Pipe, Weir & Catchment	18
6.4.3 Level Indicator Pipe	18
6.4.4 Vents	18
6.4.5 Lighting	18
6.4.6 Instruments & Control Systems	18
6.5 SITE IMPROVEMENTS	18
7 OPINION OF PROBABLE COST FOR RECOMMENDED IMPROVEMENTS	19

APPENDICES

A - Site Map

B - Standard Inspection Form

C - Site Photographs

D - Preliminary Design Report – Structural Condition Assessment

E - Summary of Ratings for Physical Condition, Performance and Rules

EXECUTIVE SUMMARY

On December 19, 2013, the Town of Addison retained Kleinfelder Central Inc. (Kleinfelder) to furnish engineering services associated with the tank evaluation and development of a CIP for the Town's water storage facilities. The scope of services provided by Kleinfelder for the purposes of this project included the observation of tank systems, preparation of recommendations and engineer's opinion of probably cost, and the development of a risk based Capital Improvement Plan.

A comprehensive evaluation and assessment of Celestial Ground Storage tank was performed by the Kleinfelder team. The assessment involved data collection, review of the reports and plans of the existing facilities, interviews with the Town staff, and field inspections of assets. The field inspection was conducted on January 27, 2014, and the detailed findings are described in this report. Data and estimated construction costs were inserted into a database which is able to organize the data to develop a list of potential Repair and Replacement (R&R) projects for all the inspected existing assets.

The Celestial GST has been operating since 1988. In general, over the years, the GST has been well maintained. During the assessment some assets were observed to be in poor condition. The entire list of the observations and recommendations for all the assets and various systems can be found in sections 5 and 6 of this report. However, below is the brief summary of the observations and recommendation:

- Coating: The coating system is mainly for aesthetic purposes and is in good condition.
- Structural: The exterior roof slope is not in compliance with TCEQ standard of 0.75 inches/foot. It is recommended to modify the roof to be in compliance or a waiver shall be requested from TCEQ. There is minor cracking in the shell and roof that should be monitored. The caulk between the roof and the shell is failing; it is recommended the caulk be replaced to ensure a positive seal from the environment.
- Safety & Security: The interior ladder has ladder cages and cable climb device. It is unnecessary to have both and therefore it is recommended the ladder cage be removed.
- Operational: The overflow weirs are severely corroded, it is recommended that both weirs are replaced.

**PRELIMINARY EVALUATION AND ASSESSMENT REPORT
CELESTIAL 6.0 MG GROUND STORAGE TANK**

1 PURPOSE

The purpose of this report is to describe the procedures that were undertaken to complete the evaluation and assessment, to record observations, and to present the resulting replacement and rehabilitation (R&R) recommendations for the Town of Addison's 6 million gallon (MG) Celestial Ground Storage Tank (GST).

A comprehensive evaluation and assessment is critical to the Town's vision for implementing asset management for its water storage facilities. The assessment involves collection of data through review of existing reports and plans for existing facilities, interviews with Town staff, and field inspections of assets. Data and estimated replacement costs are then compiled into a database which is able to organize the data to develop a list of potential R&R projects for existing assets. The results of this assessment are detailed in this report and will be used in conjunction with the results from other tank assessments to develop the overall CIP.

2 BACKGROUND

On December 19, 2013, the Town of Addison engaged Kleinfelder to “furnish engineering services associated with the development of a CIP for the Town's water storage facilities”. The scope of services to be provided by Kleinfelder for the purposes of this project includes:

- Observation of tank systems – structural, safety and security, operational, and sanitary;
- Preparation of recommendations and engineer's opinion of probable cost; and
- Development of a risk based Capital Improvement Plan for the tanks.

Ultimately, Kleinfelder will evaluate each tank in terms of its physical and operating performance. The assessment and other inputs by Town staff will be used to determine the likelihood and consequence of failure (or critically) for each tank. Kleinfelder will develop planning estimates of the costs to repair tank deficiencies observed and will develop a defensible prioritization of repairs as a CIP.

3 EXISTING FACILITY INFORMATION

The site is located in an area consisting of mostly residential development and is surrounded by trees along the tank perimeter. There are two roadways within approximately 100' north of the tank site. There are three buildings located at the site. The pump station is located on the southwest corner and the flow meter vault is located on the northeast corner of the property. There is a small staging area to the west of tank. A gate provides sufficient entry into the secured site, which is relatively level and covered mostly with grass. An 8-foot chain link fence surrounds the site with wrought iron fencing bordering the front of the site. Access to the tank is gained from Celestial Road. A site plan of the existing tank facility is shown in Appendix B.

The tank is a 6 MG concrete-constructed ground storage tank. The foundation consists of a slab-on-grade concrete footing over a compacted aggregate subgrade. The walls of the tank consist of composite precast concrete wall panels finished with pneumatic mortar. The base of the walls also consists of encased prestressed galvanized cables. The roof structure consists of a seven and a half-inch (7½-in.) reinforced concrete flat slab supported by an interior column grid consisting of sixty-nine (69) columns. The columns are sixteen inches (16 in.) in diameter and include three and a half foot (3.5 ft.) rectangular concrete capitals at the top (1.08 ft. deep) and rectangular concrete bases at the bottom. The concrete bases are four feet by four feet (4.0 ft. x 4.0 ft.). The roof hatch is a Bilco hatch and the ladder access for the interior of the tank is caged. There is a single vent located near the eastern edge of the roof. The inlet piping on the roof is supported by one concrete pipe support. The tank location slopes in grade from the north to the south exposing an additional ten to twelve feet of the tank on the lower side.

Table 1 – Facility Information

Capacity (MG)	6MG	Year Built	1988
Height of Tank (ft)	26 feet	Tank Builder	Preload Co., Inc.
Diameter of Tank (ft)	206 feet	Exterior Coating	Grout
Inlet Pipe Size (in)	36 inch	Interior Coating	None
Outlet Pipe Size (in)	(2) 42 inch	Tank Type	Ground Storage Tank
Overflow Pipe Size (in)	(2) 24 inch	Tank Class	Concrete
Overflow Elevation (ft)	598.42 feet	Pressure Zone I.D.	NA – Only 1 PZ
Sidewater Depth (ft)	24 feet	Tank I.D.	Celestial

4 PROJECT APPROACH

The evaluation and assessment included a field inspection of key components of various tank systems by a multi-discipline engineering team licensed and experienced in the areas of civil/sanitary engineering, structural engineering, and environmental engineering as well as coating specialists. Personnel from Kleinfelder, Inc., Nathan D. Maier Consulting Engineers, Inc. (NDM) and Boswell's Consulting Testing Services conducted the field inspection on Monday, January 27, 2014.

The inspection was performed in accordance with AWWA D110-04 "*Wire- and Strand-Wound, Circular, Prestressed Concrete Water Tanks*" and Section 290.46(f)(3)(D)(ii) of the Texas Commission on Environmental Quality's *Rules and Regulations for Public Water Systems*.

Field inspection of exterior systems was limited to those conditions that could be directly observed from ground and elevated surfaces including visual inspection and observation of noise, odor and vibration. Inspection of interior systems was performed by a float and via diving. The scope of the inspection and evaluation did not include in-depth electrical, instrumentation or controls (EIC) investigations; however, a general visual observation was made of the functionality of the EIC systems.

The information gathered during the condition assessment provides a standardized record of the asset condition specific to each discipline. Data collected for each asset included: condition, performance, rule (regulatory), and discipline specific data as applicable. In addition, other relevant information, such as recent performance history, and design and sizing criteria was gathered where available, and the existing condition of all assets was documented with digital photos. To standardize the process of determining an asset's condition, specific discipline-related questions were answered for each asset. Kleinfelder's Standard Inspection Form and discipline questions are presented in Appendix A. The assessment also included assigning criticality to each major asset. Data from the assessment was organized for entry into the VueWerks database.

Following data population and discussions with the Town of Addison, Kleinfelder developed three (3) separate lists of potential R&R projects. These lists were based on three (3) different

criteria: physical condition, repair cost, and risk. Based on specific criteria, key projects from each list were used to develop a single list of R&R projects. The developed list will be used in conjunction with the master planning or master plan to develop a CIP for water storage facilities.

4.1 DEFINITIONS

The rating scale used in the inspection and evaluation of each major component is shown in Table 2. Each component was assigned a value based on the percentage of the value of the component that was required to return each component to essentially new condition (i.e., restored to original physical condition, no performance issues, etc.). This scale is an internationally accepted, industry-wide standard for designating condition and performance. The terms have been adapted from *International Infrastructure Management Manual* (IPWEA, 2006).

Table 2 – Rating Scale for Physical Condition and Performance

Rating	Physical Condition	Performance
1 - Excellent	No Visible Degradation	Component Functioning as Intended
2 - Good	Slightly Visible Degradation	In-service, but Higher Than Expected O&M
3 - Moderate	Visible Degradation	In-service, but Function is Impaired
4 - Poor	Integrity of Component Moderately Compromised	In-service, but Function is Highly Impaired
5 - Critical	Integrity of Component Severely Compromised	Component not Functioning as Intended

Another rating scale (Table 3) was developed for the compliance of specific components and their associated rules. Specifically for this report, Kleinfelder focused on Texas Commission on Environmental Quality (TCEQ), Federal Aviation Administration (FAA) and Occupational Safety & Health Administration (OSHA) rules.

- TCEQ Rule: 290.43 (c): External Roof Plates
- TCEQ Rule: 290.43(c)(1): Roof Ventilation Structures
- TCEQ Rule: 290.43(c)(2): Water Access Hatch
- TCEQ Rule: 290.43(c)(3): Overflow Flappers
- TCEQ Rule: 290.43(c)(4): Water Level Indicator

- TCEQ Rule: 290.43(c)(10): Manway Access Hatch
- TCEQ Rule: 290.43(e): Security Fence
- OSHA Rule: 1910.27(b)(1)(ii): Ladder Rungs
- OSHA Rule: 1910.146(c)(2): Permits
- OSHA Rule: 1917.118(e)(1): Fall Protection
- OSHA rule: 1917:118(c)(1): Broken Ladders
- FAA Rule: Aircraft Warning Lights

Table 3- Rating Scale for Compliance with Rules

Rating	Rule (or Regulation)
1 - Exceeds	Component Functioning as Intended by Rule
2 - Acceptable	In-service, but Function Minimally Meets Rule
3 - Needs Improvement	In-service, but Function Does Not Meet Rule

5 EVALUATIONS AND ASSESSMENT RESULTS

To minimize City costs and risks with draining of the ground storage tank, Kleinfelder proposed to inspect the interior of the tank (below high water level) via diving. A “float” inspection was conducted of the roofing system and areas above the high water level.

Although not all OSHA regulations apply to this inspection, any unsafe condition or violations of current OSHA, which were observed, are noted in this report. In addition, an effort was made to identify applicable components complying with TCEQ and FAA rules.

The section below provides an overview of observations and issues that have been identified for each system of the tank. In addition, ratings are provided for applicable components for each system. Specific tank systems include:

Table 4 – Tank Systems

Tank System	Components
Structural	
Tank Exterior Structural and Appurtenances	<ul style="list-style-type: none"> • Tank foundation • Roof panels and shell panels • Access ladders • Roof accessories, vents, and roof hatches • Exterior valves and piping connected to the tank, inlet/outlet piping, tank drain, overflow pipe, and flap valve
Tank Interior Structural and Appurtenances	<ul style="list-style-type: none"> • Roof plates and roof framing • Tank and appurtenances at floor level • Overflow weir, and pipe • Ladder, platforms, walkways, and Crow's Nest • Level sensor/transmitter and sample taps
Safety & Security	
Safety and Security Features	<ul style="list-style-type: none"> • Security cameras, alarms, sensors and access controls • Fall protections systems • Ladders • Safety devices • FAA warning lights • Fencing, gates, lighting and access points

Table 4 – Tank Systems (continued)

Tank System	Components
Operational	
Tank Site Evaluation	<ul style="list-style-type: none"> • Paved areas including access drive and parking • Overflow splash pads or catchment structures • Site grading and drainage, drain piping, detention ponds, headwalls and culverts
Pipe and Valve Vaults	<ul style="list-style-type: none"> • Vault structure • Access hatch, manhole covers, ladders, safety railing and platforms • Pipe and valves • Pipe and valve coating • Pipe and valve supports and thrust restraint system • Ventilation, lighting, sump pumps and drains
Instrumentation and Control Systems	<ul style="list-style-type: none"> • Pressure, level and valve controls • SCADA and Remote Terminal Units • Interior, exterior lighting and obstruction lights
Sanitary	
Pathways for Contamination Evaluation	<ul style="list-style-type: none"> • Roof and walls • Sleeves and shielding • Roof hatches • Roof drainage • Venting • Screening • Overflows

5.1 COATING SYSTEM

The tank exterior was recoated in the year 2008 based on the information provided by the Town of Addison. The shell coating is good condition. There is no Cathodic Protection system installed at this tank. The roof coating is in moderate condition. An overall Physical Condition Rating of 2 and a Performance Rating of 1 were assigned to the coating system. The coating system should be re-inspected and reevaluated in 3 to 5 years, with the anticipation that complete coating replacement will be required in 5 years.

5.1.1 Exterior

- Tank Shell – The tank shell have a grout/stucco coating. (See Appendix C, Photo 1)

Date of last re-coating: 2008

Coating materials used in last re-coat: Not Available

Coating method: Not Available

General condition of coating: The tank shell coating typically appears to be in good condition.

Adhesion of coating: Adhesion tests were not performed as a part of the inspection due to the coating being grout/stucco and the tank being concrete.

Thickness of coating: Not Available

- Tank Roof – The tank roof has a grout/stucco coating. (See Appendix C, Photo 10)

Roof type and structure: Concrete

Date of last re-coating: 2008

Coating materials used in last re-coat: Not Available

Coating method: Not Available

General condition of coating: The roof coating typically appears to be in good condition.

Adhesion of coating: Adhesion tests were not performed as a part of the inspection due to the coating being grout/stucco and the tank being concrete.

Thickness of coating: Not Available

5.1.2 Interior

The Interior of the tank has no coating.

5.2 STRUCTURAL

Based on NDM's Condition Assessment Report in Appendix D, structural issues include missing vegetation around the base of the tank which is causing erosion around the foundation. Cracking on the exterior walls will need to be addressed if they become more significant. Cracking on the exterior roof will need to be addressed if they become more significant. Spalled and exposed reinforcing areas on the interior roof need repair. Cracking on the interior floor needs to be sealed. The overflow structure and piping is corroded. The sonic level transmitter is corroded. Consequently, the structural system was assigned an overall Physical Condition Rating of 2, Performance Rating of 2 and

Rule Rating of 1. It is recommended that the structural repairs be completed within the next 1-3 years.

5.2.1 Exterior & Appurtenances

- Roof – The roof is made up of four (4) concrete sections. Some moderate cracking was observed on exterior roof. Some cracking appears to be all the way through the concrete sections. (See Appendix C, Photos 1-4) The slope of the roof is 0.25 inch per foot which does not meet TCEQ Subchapter D Rules and Regulations for Water Systems 290.43(c). TCEQ requires that “no area of the roof shall have a slope of less than 0.75 inch per foot.”
- Grout/Caulk – The grout between the roof and the shell wall was observed to be in poor condition. There appears to be some areas that the grout has failed and has allowed a gap between the roof and shell that exceeds 0.062 inches.
- Shell – The exterior shell is concrete with a grout coating. Some cracking was observed in the shell. The exterior shell typically appears to be in good condition (See Appendix C, Photos 13 and 14).

5.2.2 Interior & Appurtenances

- Roof – The roof is made up of four (4) concrete sections. Some moderate cracking was observed on the interior with some efflorescence. Some surface failure (spalling) was also observed on the interior roof. Corrosion of the reinforced steel chairs and some exposed reinforced steel was observed. (See Appendix C, Photos 5-9)
- Columns – There are 69 16-inch diameter columns with 3-foot 6-inch cone shaped column caps and 4-ft X 4-ft square bases. (See Appendix C, Photos 10-12)
- Grout/Caulk – The grout between the interior roof panels typically appears to be in good condition. The grout between the floor panels appears to be in good condition, some sedimentation has collected around the joints.
- Shell – The interior shell is concrete. The interior shell typically appears to be in good condition (See Appendix C, Photo 17).

5.2.3 Foundation

The foundation was not accessible for observation.

5.3 SAFETY & SECURITY

In general, the site's fencing complies with TCEQ Subchapter D Rules and Regulations for Water Systems 290.43(e). Fall protection and ladder rungs are in compliance with OSHA 1910. The workplace contains permit spaces that are adequately identified with signage. An overall Physical Condition Rating of 2, Performance Rating of 2, and Rule Rating 2 were assigned to the safety and security components.

5.3.1 Ladders

- Interior

The interior ladder is stainless steel with a ladder cage and a cable climb system. The overall condition of the ladder is good. No severe corrosion was observed on the ladder. The cable climb system has some visible corrosion. (See Appendix C, Photos 52-55).

Safety climb device: Yes – Cable Climb

General condition of coating: Not Applicable

Degree of rusting: Low

Condition of metal: Good

- Exterior

There is no exterior Ladder.

5.3.2 Roof Hatch

The roof hatch is equipped with a padlock and proper confined space signage. (See Appendix C, Photo 51).

Hatch type: 4 foot x 4 foot Stainless Steel Bilco Hatch

General condition of coating: Not Applicable

Degree of rusting: Low

Condition of metal: Good

5.3.3 Fencing & Gate

Fencing type: 8-foot chain link and wrought iron (See Appendix C, Photos 56 and 57)

Gate type: Automatic Swinging Gate (See Appendix C, Photo 58)

Access to site: Access to site is from Celestial Road – north of site – via a security gate.

General condition of coating: Good

Degree of rusting: Low

Condition of metal: Good

5.4 OPERATIONAL

An overall Physical Condition Rating of 2, Performance Rating of 2, and Rule Rating 1 were assigned to operational components.

5.4.1 Inlet Pipe & Valves

Size: 36-inch diameter ductile iron inlet pipe with cast iron elbows. (See Appendix C, Photos 22-25).

General condition of coating: Exterior pipe coating is in good condition.

Degree of rusting: Not Accessible

Condition of metal: Not Accessible

5.4.2 Outlet Pipe & Valve

Size: (2) 42-inch ductile iron outlet pipes. (See Appendix C, Photos 26 and 27)

General condition of coating: Not Accessible

Degree of rusting: Not Accessible

Condition of metal: Not Accessible

5.4.3 Overflow Pipe, Weir & Catchment

Type and size: (2) 24-inch ductile iron overflow pipes with cast iron flap valves. Each pipe has a 4-foot 2-inch x 4-foot 2-inch weir box. (See Appendix C, Photos 28-43)

Details for catchment: No overflow catchment. Concrete splash pad. (See Appendix C, Photos 28 and 37). The overflow drains to storm drain located at north of the tank site.

General condition of coating: Poor

Degree of rusting: Both overflow weir boxes are severely corroded. (See Appendix C, Photos 32-35 and 40-42) The bolts on the interior flanges are severely corroded. (See Appendix C, Photos 36 and 43) Corrosion was observed on the interior of the pipes near the flap gates. Corrosion on overflow pipe 1 was more severe than overflow pipe 2. (See Appendix C, Photo 31)

Condition of metal: NA

5.4.4 Level Indicator

Type and size: (1) abandoned unknown size level indicator pipe.

General condition of coating: Poor

Degree of rusting: Severe

Condition of metal: Poor

5.4.5 Vents

Type and size: (1) 48-inch roof vent with a 16-inch fine mesh screen which meets TCEQ Subchapter D Rules and Regulations for Water Systems 290.43(c) (1). The full in-depth analysis will be required to confirm the proper vent sizing.

General condition of coating: Good

Degree of rusting: Low

Condition of metal: Good

5.4.6 Lighting

There is no lighting near the tank.

5.4.7 Instrument & Control Systems

The Wonderware SCADA software is a Windows based system located in the Pump Station and is at least 15 years old. The current SCADA system and all other electrical systems are operable and functions on a daily basis based on the information received by the Town of Addison.

5.5 SANITARY

Overall, potential pathways for contamination from rodents, insects, etc. have been eliminated. An overall Physical Condition Rating of 2, Performance Rating of 2, and Rule Rating 1 were assigned to the sanitary components.

5.5.1 Roof Hatch

The roof hatch meets TCEQ Subchapter D Rules and Regulations for Water Systems 290.43(c) (2). The hatch is more than 30-inches

5.5.2 Roof Vent

48-inch roof vent 16-inch fine mesh screen which meets TCEQ Subchapter D Rules and Regulations for Water Systems 290.43(c) (1). The vent size needs more detailed evaluation for the proper sizing.

5.5.3 Overflow

The overflow flap gate complies with TCEQ Subchapter D Rules and Regulations for Water Systems 290.43(c) (3). The gap between the flap gate and the flange is less than 1/16-inch.

6 CONCLUSIONS AND RECOMMENDATIONS

The Celestial GST has been operating since 1988. Over the years, the GST has been well maintained; this fact is evident in the small number of Physical Condition Rating of 4 and 5 identified during the assessment. Currently, the Town of Addison has no plans for improvement of this asset.

To ensure accurate and timely identification of future R&R projects, it is recommended that evaluations and assessments be conducted on a regular basis and that the components of the various tank systems identified for the R&R projects be monitored and assessed prior to implementation of the project.

Accordingly, it is recommended that the components in poor condition (Condition 4 or 5) be assessed annually, and a comprehensive assessment of all of the components of the tank systems be conducted every 3 to 5 years.

The assessment should be conducted by a team of individuals including O&M staff and engineering staff, and discipline specialists. Information collected during future assessments should mirror the work completed for this work. Digital photos of the assets should also be taken to document the existing condition of each component of the various tank systems.

6.1 COATING SYSTEM

6.1.1 Exterior

The grout coating system on the exterior of the tank is in good condition. The coating system is for aesthetics and does not need to be replaced for the functionality of the tank. There are no improvements recommended for the coatings.

6.1.2 Interior

Level Indicator Pipe – the level indicator pipe is in poor condition with severe corrosion. It is recommended that the coating on all surfaces of the pipe be

completely removed by abrasive blasting and surfaces prepared to an SSPC-SP10 Near-White Blast Cleaning standard. A 100% solids elastomeric NSF 61 approved coating system is recommended for application on any interior tank surfaces.

Overflow Structure and Piping – the overflow weir and bolts are in poor condition, it is recommended in addition to the replacement that the new weir sections and the pipe be abrasive blasted and surfaces prepared to an SSPC-SP10 Near-White Blast Cleaning standard. A 100% solids elastomeric NSF 61 approved coating system is recommended for application on any interior tank surfaces.

6.2 STRUCTURAL

6.2.1 Exterior & Appurtenances

- Roof (Option 1) – the exterior roof is in moderate condition, it is recommended that the cracking is monitored. (See appendix E) The slope of the roof does not meet TCEQ standard of 0.75 inches. It is recommended that a waiver is requested from TCEQ to keep the slope less than 0.75 inches per foot. If a waiver is received the roof should be modified to have positive drainage to avoid ponding
- Roof (Option 2) – the exterior roof is in moderate condition, it is recommended that the cracking is monitored. (See appendix E) The slope of the roof does not meet TCEQ standard of 0.75 inches. If a waiver from TCEQ is not received, it is recommended that the roof shall be modified to meet the TCEQ standards. Any new additional material added to modify the roof will need to be evaluated structurally so that the integrity of the tank structure is not compromised with the additional weight.
- Grout/Caulk – the grout between the roof plates and the shell is in poor condition. It is recommended that the grout be repaired to provide a positive seal between the environment and the tank.
- Shell – the shell is in good condition, some cracking was observed on the shell it is recommended that the cracks be monitored. (See appendix E).

6.2.2 Interior & Appurtenances

- Roof – the interior roof is in moderate condition, it is recommended that the spalled and cracked areas are monitored and repaired during the next rehabilitation.
- Columns – the columns are in good condition, no improvements are recommended.

- Grout/Caulk – the interior grout is in good condition, no improvements are recommended.
- Shell – the interior shell is in good condition, no improvements are recommended.

6.2.3 Foundation

The foundation was not accessible for observation.

6.3 SAFETY & SECURITY

6.3.1 Ladders

The interior ladder is in good condition, the cable climb device shows some signs of degradation. It is recommended that the ladder cage be removed from the ladder and the cable climb system be replaced with a safety climb rail system.

6.3.2 Roof Hatch

The roof hatch is in good condition, no improvements are recommended.

6.3.3 Fencing & Gate

The fencing and gates are in good condition, no improvements are recommended.

6.4 OPERATIONAL

6.4.1 Inlet Pipe & Valves

The inlet pipe and valves are in good condition, no improvements are recommended.

6.4.2 Overflow Pipe, Weir & Catchment

The overflow weirs and bolts on the interior flanges are in poor condition with severe corrosion. It is recommended that the weirs and bolts be replaced during the next rehabilitation. The overflow runs to the storm drain located north of the tank site.

6.4.3 Level Indicator Pipe

The level indicator pipe is in poor condition. See coating recommendations in section 6.1.2.

6.4.4 Vents

The roof vent is in good condition, no improvements are recommended.

6.4.5 Lighting

The lighting is in good condition, no improvements are recommended.

6.4.6 Instruments & Control Systems

The instrument and control systems are in good condition, no improvements are recommended.

6.5 SITE IMPROVEMENTS

There is minor erosion around the tank base due to absent vegetation in the area. It is recommended that the area be re-vegetated to avoid further erosion damage. (See Appendix E). There may be necessity of either installing the side walk around the tank perimeter or provide a gravel side walk for the easy access of the tank perimeter for visual inspection and/or routine maintenance.

7 OPINION OF PROBABLE COST FOR RECOMMENDED IMPROVEMENTS

Tank System/ component	Description	Estimated Cost
Coating – Level Indicator	Abrasive blast and recoat sonic level indicator and overflow weir and piping	\$7,500
Structural – Interior Roof	Repair Spalling and Reinforcing Corrosion (Assumes 400 SF Spalling Repair)	\$20,000
Structural – Exterior roof	Add material to bring roof slope to 0.75 inches per foot including the required structural modifications.	\$1,000,000
Structural – Interior Floor	Seal cracking (Assumes 200 LF Repair)	\$5,400
Structural – Overflow	Replace the overflow weirs and corroded bolts	\$5,000
Safety – Ladder	Remove ladder cage and cable climb system. Install safety climb rail system.	\$20,000
Site Improvements	Revegetation to control erosion	\$7,500
	Sub Total	\$1,065,400
	Contingency (15%)	\$159,810
	Engineering (15%)	\$159,810
	Total Cost	\$1,385,020



APPENDIX A
Standard Inspection Form



Standard Inspection Form

Inspection Date	01/27/14	Time	9:00 AM	Project City	Addison
Project Number	Celestial GST			Project State/Country	TX / US
Project Name	CIP - Water Storage Facilities				

Client Contact Information

Client Name	Town of Addison	Contact Department	Infrastructure Operations & Service
Property Owner	Town of Addison	Contact Name	Jason / Shroyer
Client Project No.		Contact Phone	972-450-2849
Client P.O.		Contact Email	jshroyer@addisontx.gov
Site I.D.			
Project Cost		O&M Plan for Tanks	
		Plan Prepared By	/

Site and Inspector Information

Type of Inspection	CIP - Water Storage Facilities	Tank Class	Ground Storage
Date Filled		Tank Type	Concrete
Date Drained		Name of Firm	Kleinfelder
Date of Bac-T		Firm's Phone Number	
Bac-T Result		Inspector's Name	Lisa / Larson

Notes of Access to Property:

General Comments Related to Property & Tank:

Overview of Property Information

Pressure Zone I.D.		Year Built	1976
Inlet Pipe Size (In)	36	Capacity (MG)	6
Outlet Pipe Size (In)	(2) 42	Diameter of Tank (ft)	206
Overflow Pipe Size (In)	(2) 24	Height of Tank (ft)	25' 6"
Exterior Coating		Overflow Elevation (ft)	
Interior Coating		Sidewater Depth (ft)	
Rehabilitated		Tank Builder	Per load Co, Inc.
Year Rehabilitated		Age of Tank	38

If information related to rehab available?

If yes, please describe rehabilitation:

General Info

Inspection Date	01/27/14	Time	9:00 AM	Project City	Addison
Project Number	Celestial GST			Project State/Country	TX / US
Project Name	CIP - Water Storage Facilities				

Capital Expenditures

Describe in detail Repairs, Replacements or Capital Improvements	Identified Cost	Status

Site and Vicinity Comparison Data

Is the area declining or distressed	No	Percent Use - %	
Is there any new construction near the tank	No		
Major Buildings:	1. Name or Type	Single Family	100%
	Distance	Multifamily	0%
	2. Name or Type	Commercial	0%
	Distance	Industrial	
		Undeveloped	0%

Describe site, surrounding land use & other pertinent information:

Other Information

Additional Collateral Description Information

Standard Inspection Form

Inspection Date Time
 Project Number
 Project Name

Property City
 Property State/Country /

Operational Assessment - Physical, Performance & Rule*Operational Assessment*

ID	Physical	Perform	Rule	Representative Components (Not all-inclusive)	Comments
Inlet Pipe	2	2	Not Applicable	36-inch diameter ductile iron inlet pipe with cast iron elbows.	None
Inlet Pipe Valve	Not Accessible	Not Accessible	Not Applicable	Not Accessible	Not Accessible
Outlet Pipe	2	2	Not Applicable	(2) 42-inch diameter ductile iron outlet pipes.	None
Outlet Pipe Valve	Not Accessible	Not Accessible	Not Applicable	Not Accessible	Not Accessible
Overflow Pipe & Weir	3	2	1	(2) 24-inch diameter ductile iron overflow pipes with cast iron elbows and 4-foot 2-inch weir boxes. Concrete splash pads.	The overflow weirs were observed to be severely corroded. Corrosion was also observed on the bolts on the interior flanges. Both flap gates meet the TCEQ Subchapter D Rules and Regulations for Water Systems 290.43-c-3 requirement of no more than a 1/16-inch gap allowed.
Overflow Pipe Catchment	Not Applicable	Not Applicable	Not Applicable	Not Applicable	Not Applicable
Drain Pipe & Valve	Not Applicable	Not Applicable	Not Applicable	Not Applicable	Not Applicable
Washout Pipe	Not Applicable	Not Applicable	Not Applicable	Not Applicable	Not Applicable
Vents	2	2	1	48-inch with 16-inch fine mas screen	TCEQ Subchapter D Rules and Regulations for Water Systems 290.42-b-7 states all openings to the atmosphere should be covered with 16-mesh or finer corrosion-resistant screening. Roof vent screen is in compliance.

Inspection Date	01/27/14	Time	9:00 AM
Project Number	Celestial GST		
Project Name	CIP - Water Storage Facilities		

Property City	Addison
Property State/Country	TX / US

Electrical	4	Not Accessible	Not Applicable	Conduit to the Sonic Level Transmitter. Conduits to roof hatch (need info on what these are for)	The conduits were observed to be broken and taped over. It is unknown whether any of the conduits have active cable.
Lighting	Not Applicable	Not Applicable	Not Applicable	Not Applicable	No lighting was observed.
Instrumentation & Control Systems	Not Applicable	Not Applicable	Not Applicable	Not Applicable	No Instrumentation & Control Systems were observed.

Exterior - Additional description of the tank conditions:

Interior - Additional description of the tank conditions:

Recommended Improvements

Identify Item and Describe Condition (including location)	Rating	Photo #	Life Safety	Est. Cost

Standard Inspection Form

Inspection Date Time
 Project Number
 Project Name

Property City
 Property State/Country /

Safety & Security Assessment - Physical, Performance & Rule

Safety & Security Assessment

ID	Physical	Perform	Rule	Representative Components (Not all-inclusive)	Comments
Roof Hatch	2	2	1	4-foot square Bilco Roof Hatch	TCEQ Subchapter D Rules and Regulations for Water Systems 290.43-c-2 states at least one opening of 30-inch or more is required. In compliance
Tie-off Point	Not Applicable	Not Applicable	1	Not Applicable	No exterior ladder due to the tank being partially below ground.
Painters Access Hatch	Not Applicable	Not Applicable	Not Applicable	Not Applicable	Not Applicable
Roof Perimeter Railing	Not Applicable	Not Applicable	Not Applicable	Not Applicable	Not Applicable
Roof Landing	Not Applicable	Not Applicable	Not Applicable	Not Applicable	Not Applicable
Railing	Not Applicable	Not Applicable	Not Applicable	Not Applicable	Not Applicable
Platform	Not Applicable	Not Applicable	Not Applicable	Not Applicable	Not Applicable
Immediate Landing	Not Applicable	Not Applicable	Not Applicable	Not Applicable	Not Applicable
Ladder	2	2	1	Interior ladder with a ladder cage and cable climb.	Ladder cage should be removed and a safety climb rail should be installed.
Lockable Ladder Guard	Not Applicable	Not Applicable	Not Applicable	Not Applicable	Not Applicable

Safety & Security Assessment

Inspection Date Time
 Project Number
 Project Name

Property City
 Property State/Country /

Shell Opening (Manway)	Not Applicable	Not Applicable	Not Applicable	Not Applicable	Not Applicable
Fencing & Gate	2	2	1	6-foot chain-link fence with wrought iron fencing at front and gate.	

Exterior - Additional description of the tank conditions:

Interior - Additional description of the tank conditions:

Recommended Improvements

Identify Item and Describe Condition (including location)	Rating	Photo #	Life Safety	Est. Cost

Standard Inspection Form

Inspection Date	01/27/14	Time	9:00 AM
Project Number	Celestial GST		
Project Name	CIP - Water Storage Facilities		

Property City	Addison
Property State/Country	TX / US

Coatings Assessment - Physical, Performance & Rule

Coatings Assessment

ID	Physical	Perform	Rule	Representative Components (Not all-inclusive)	Comments
Interior Coating	Not Applicable	Not Applicable	3	Not Applicable	Not Applicable
Exterior Coating	2	1	Not Applicable	Grout coating on the roof and shell	Coating on the roof and shell is typically in good condition.



Standard Inspection Form

Inspection Date	01/27/14	Time	9:00 AM
Project Number	Celestial GST		
Project Name	CIP - Water Storage Facilities		

Property City	Addison
Property State/Country	TX / US

Client Information & Interview

Client Name	Town of Addison	Phone Number	972-450-2849
Name of Interviewee	Jason Shroyer	Email Address	jshroyer@addisontx.gov
Role or Title	Assistant Director	Length of Time in Dept	
Department	Infrastructure Operations & Services		

In your opinion, how does the tank perform compared to similar tanks in your system?

In the past 12 months, have there been any significant issues with the tank?

If yes, explain the type of issue, resolution & cost associated:

In the past 12 months, to the best of your knowledge, have any code violations (TCEQ and/or OSHA) occurred?

If yes, please describe the violation, the costs associated and any resolution or outstanding issues:

Is the tank undergoing any planned rehab in the next 1-2 years?

If yes, explain the type of rehab and estimated costs:

Are there any water quality issues associated with the tank?

If yes, please explain:

Are there any water pressure issues associated with this tank?

If yes, please explain:

Are there any improvements you would like to recommend?

If yes, please explain:

Roof sometimes holds water. Might need to address the drainage off the top of the tank. Safety cage over discharge outlet.

Other Information or Comments:



Standard Inspection Form

Inspection Date Time
 Project Number
 Project Name

Property City
 Property State/Country /

Limitations of Field Investigation

Did you experience any of the following limitations to performing this field assessment: (Choose Yes/No)

Management? Operations unavailable for interview or operations experience on the site is less than six months	<input type="text"/>
Interior of tank unavailable for assessment due to accessibility	<input type="text"/>
Significant portions of the tank site were unavailable for assessment	<input type="text"/>
Other	<input type="text"/>
None	<input type="text"/>
Comment:	<input type="text"/>

Criticality Assessment

1. Public Health & Safety (Choose the one that applies from the drop down menu):

Comment:

2. Effect on Customer (Choose the one that applies from the drop down menu):

Comment:

3. Environmental Impact (Choose the one that applies from the drop down menu):

Comment:

4. Cost to Repair (Choose the one that applies from the drop down menu):

Comment:

Overall Criticality Rating

Overall Rating Scale:

Comment:

Inspector Information


Seller/Service Certification Date:

First Name:
 Last name:
 Title:
 Phone Number:
 Email Address:



APPENDIX B
Site Map

Copyright NCTCOG



6 MG Celestial GST

DFWMaps.com

DISCLAIMER

This data has been compiled for NCTCOG. Various official and unofficial sources were used to gather this information. Every effort was made to ensure the accuracy of this data, however, no guarantee is given or implied as to the accuracy of said data.





APPENDIX C
Site Photos

Standard Inspection Form

Inspection Date	01/27/14	Time	9:00 AM
Project Number	Celestial GST		
Project Name	CIP - Water Storage Facilities		

Property City	Addison		
Property State/Country	TX	/	US

Photos



Photo 1	Roof of 206-foot interior diameter tank with slope of 0.25 inch per foot
Category: Structural	



Photo 2	Roof
Category: Structural	

Standard Inspection Form

Inspection Date	01/27/14	Time	9:00 AM
Project Number	Celestial GST		
Project Name	CIP - Water Storage Facilities		

Property City	Addison		
Property State/Country	TX	/	US

Photos



Photo 3	Roof
Category: Structural	



Photo 4	Roof - Construction Joint
Category: Structural	

Standard Inspection Form

Inspection Date	01/27/14	Time	9:00 AM
Project Number	Celestial GST		
Project Name	CIP - Water Storage Facilities		

Property City	Addison	
Property State/Country	TX	/ US

Photos



Photo 5	Roof - Severe Cracking Observed
Category: Structural	



Photo 6	Interior Roof - Construction Joint
Category: Structural	

Standard Inspection Form

Inspection Date	01/27/14	Time	9:00 AM
Project Number	Celestial GST		
Project Name	CIP - Water Storage Facilities		

Property City	Addison		
Property State/Country	TX	/	US

Photos



Photo 7	Interior Roof - Typical Spalling Observed
Category: Structural	



Photo 8	Interior Roof - Construction Joint
Category: Structural	

Standard Inspection Form

Inspection Date	01/27/14	Time	9:00 AM
Project Number	Celestial GST		
Project Name	CIP - Water Storage Facilities		

Property City	Addison		
Property State/Country	TX	/	US

Photos



Photo 9	Interior Roof - Spalling and Corroded Rebar Observed
Category: Structural	




Photo 10	Column - 1-foot 4-inch Square Cap with 16-inch Column
Category: Structural	

Standard Inspection Form

Inspection Date	01/27/14	Time	9:00 AM	Property City	Addison
Project Number	Celestial GST			Property State/Country	TX / US
Project Name	CIP - Water Storage Facilities				

Photos




Photo 11	Column - 16-inch
Category: Structural	



Photo 12	Column - 4-foot Square Base with 16-inch Column
Category: Structural	

Standard Inspection Form

Inspection Date	01/27/14	Time	9:00 AM
Project Number	Celestial GST		
Project Name	CIP - Water Storage Facilities		

Property City	Addison		
Property State/Country	TX	/	US

Photos




Photo 13	Shell - 6-1/2-inch Precast Composite Core Wall with 1/2-inch CL
Category: Structural	



Photo 14	Shell
Category: Structural	

Standard Inspection Form

Inspection Date	01/27/14	Time	9:00 AM
Project Number	Celestial GST		
Project Name	CIP - Water Storage Facilities		

Property City	Addison		
Property State/Country	TX	/	US

Photos



Photo 15	Shell with Sprinkler Head
Category: Structural	



Photo 16	Shell and Roof - Observed Severe Degredation of the Joint
Category: Structural	

Standard Inspection Form

Inspection Date	01/27/14	Time	9:00 AM
Project Number	Celestial GST		
Project Name	CIP - Water Storage Facilities		

Property City	Addison		
Property State/Country	TX	/	US

Photos



Photo 17	Interior Shell and Roof
Category: Structural	



Photo 18	Water Stop
Category: Structural	

Standard Inspection Form

Inspection Date	01/27/14	Time	9:00 AM
Project Number	Celestial GST		
Project Name	CIP - Water Storage Facilities		

Property City	Addison		
Property State/Country	TX	/	US

Photos



Photo 19	Interior Floor - Cracking was Observed
Category: Structural	




Photo 20	Floor Joints
Category: Structural	

Standard Inspection Form

Inspection Date	01/27/14	Time	9:00 AM	Property City	Addison
Project Number	Celestial GST			Property State/Country	TX / US
Project Name	CIP - Water Storage Facilities				

Photos




Photo 21	Floor - Concrete pieces from the Roof were Observed
Category: Structural	



Photo 22	Inlet Pipe - 36-inch Ductile Iron Class 53
Category: Operational	

Standard Inspection Form

Inspection Date	01/27/14	Time	9:00 AM
Project Number	Celestial GST		
Project Name	CIP - Water Storage Facilities		

Property City	Addison		
Property State/Country	TX	/	US

Photos



Photo 23	Inlet Pipe - 36-inch Ductile Iron Class 53
Category: Operational	



Photo 24	Inlet Pipe - 36 Inch Ductile Iron Class 53
Category: Operational	

Standard Inspection Form

Inspection Date	01/27/14	Time	9:00 AM
Project Number	Celestial GST		
Project Name	CIP - Water Storage Facilities		

Property City	Addison		
Property State/Country	TX	/	US

Photos



Photo 25	Interior Inlet - 36-inch Ductile Iron
Category: Operational	



Photo 26	Outlet 1 - 42-inch Ductile Iron
Category: Operational	

Standard Inspection Form

Inspection Date	01/27/14	Time	9:00 AM	Property City	Addison
Project Number	Celestial GST			Property State/Country	TX / US
Project Name	CIP - Water Storage Facilities				

Photos



Photo 27	Outlet 2 - 42-inch ductile iron
Category: Operational	



Photo 28	Overflow 1 - 24-inch Cast Iron Flap Valve and Concrete Splash Pad
Category: Operational	

Standard Inspection Form

Inspection Date	01/27/14	Time	9:00 AM	Property City	Addison
Project Number	Celestial GST			Property State/Country	TX / US
Project Name	CIP - Water Storage Facilities				

Photos



Photo 29	Overflow 1 - 24-inch Cast Iron Flap Valve
Category: Operational	



Photo 30	Overflow 1 - 24-inch Cast Iron
Category: Operational	

Standard Inspection Form

Inspection Date	01/27/14	Time	9:00 AM	Property City	Addison
Project Number	Celestial GST			Property State/Country	TX / US
Project Name	CIP - Water Storage Facilities				

Photos



Photo 31	Overflow 1 - 24-inch Cast Iron - Interior Corrosion was Observed
Category: Operational	



Photo 32	Overflow 1 Weir Box - 4 feet 2 inches Wide by 4 feet 2 inches Wide
Category: Operational	

Standard Inspection Form

Inspection Date	01/27/14	Time	9:00 AM
Project Number	Celestial GST		
Project Name	CIP - Water Storage Facilities		

Property City	Addison		
Property State/Country	TX	/	US

Photos



Photo 33	Overflow 1 Weir Box - 4 feet 2 inches Wide by 4 feet 2 inches Wide
Category: Operational	




Photo 34	Overflow 1 - Turnbuckle - 1/2 inch Diameter by 6 inch
Category: Operational	

Standard Inspection Form

Inspection Date	01/27/14	Time	9:00 AM
Project Number	Celestial GST		
Project Name	CIP - Water Storage Facilities		

Property City	Addison	
Property State/Country	TX	/ US

Photos



Photo 35	Overflow 1 - 24-inch Diameter
Category: Operational	




Photo 36	Overflow 1 - 24-inch Cast Iron 90 Degree Bend
Category: Operational	

Standard Inspection Form

Inspection Date	01/27/14	Time	9:00 AM
Project Number	Celestial GST		
Project Name	CIP - Water Storage Facilities		

Property City	Addison		
Property State/Country	TX	/	US

Photos



Photo 37	Overflow 2 - 24-inch Cast Iron with Concrete Splash Pad
Category: Operational	



Photo 38	Overflow 2 - 24-inch Cast Iron Flap Valve
Category: Operational	

Standard Inspection Form

Inspection Date	01/27/14	Time	9:00 AM	Property City	Addison
Project Number	Celestial GST			Property State/Country	TX / US
Project Name	CIP - Water Storage Facilities				

Photos



Photo 39	Overflow 2
Category: Operational	



Photo 40	Overflow 2 - Weir Box - 4 feet 2 inches Wide by 4 feet 2 inches Wide
Category: Operational	

Standard Inspection Form

Inspection Date	01/27/14	Time	9:00 AM
Project Number	Celestial GST		
Project Name	CIP - Water Storage Facilities		

Property City	Addison		
Property State/Country	TX	/	US

Photos



Photo 41	Overflow 2 - 1/2-inch Diameter by 6-inch Turnbuckle
Category: Operational	



Photo 42	Overflow 2 - Weir Box - 4 feet 2 inches Wide by 4 feet 2 inches Wide
Category: Operational	

Standard Inspection Form

Inspection Date	01/27/14	Time	9:00 AM	Property City	Addison
Project Number	Celestial GST			Property State/Country	TX / US
Project Name	CIP - Water Storage Facilities				

Photos



Photo 43	Overflow 2 - 24-inch Cast Iron 90 degree Bend
Category: Operational	



Photo 44	Vent - Fiberglass with 48-inch Opening
Category: Operational	

Standard Inspection Form

Inspection Date	01/27/14	Time	9:00 AM
Project Number	Celestial GST		
Project Name	CIP - Water Storage Facilities		

Property City	Addison		
Property State/Country	TX	/	US

Photos



Photo 45	Vent - Fiberglass with 48-inch Opening
Category: Operational	



Photo 46	Pipe - 24-inch Steel Pipe for Sonic Level Transmitter (Abandoned)
Category: Operational	

Standard Inspection Form

Inspection Date	01/27/14	Time	9:00 AM
Project Number	Celestial GST		
Project Name	CIP - Water Storage Facilities		

Property City	Addison		
Property State/Country	TX	/	US

Photos



Photo 47	Electrical - Formerly for Sonic Level Transmitter
Category: Operational	



Photo 48	Electric - Formerly for Sonic Level Transmitter
Category: Operational	

Standard Inspection Form

Inspection Date	01/27/14	Time	9:00 AM
Project Number	Celestial GST		
Project Name	CIP - Water Storage Facilities		

Property City	Addison		
Property State/Country	TX	/	US

Photos



Photo 49	Transducer Tag
Category: Operational	



Photo 50	Control Building???
Category: Operational	

Standard Inspection Form

Inspection Date	01/27/14	Time	9:00 AM	Property City	Addison
Project Number	Celestial GST			Property State/Country	TX / US
Project Name	CIP - Water Storage Facilities				

Photos



Photo 51	Roof Hatch - 4-foot x 4-foot
Category: Safety & Security	



Photo 52	Interior Ladder - Stainless Steel
Category: Safety & Security	

Standard Inspection Form

Inspection Date	01/27/14	Time	9:00 AM
Project Number	Celestial GST		
Project Name	CIP - Water Storage Facilities		

Property City	Addison		
Property State/Country	TX	/	US

Photos



Photo 53	Interior Ladder - Stainless Steel Ladder Cage
Category: Safety & Security	




Photo 54	Interior Ladder - Cable Climb
Category: Safety & Security	

Standard Inspection Form

Inspection Date	01/27/14	Time	9:00 AM	Property City	Addison
Project Number	Celestial GST			Property State/Country	TX / US
Project Name	CIP - Water Storage Facilities				

Photos




Photo 55	Interior Ladder Brace
Category: Safety & Security	



Photo 56	Perimeter Fence - Chain Link
Category: Safety & Security	

Standard Inspection Form

Inspection Date	01/27/14	Time	9:00 AM	Property City	Addison
Project Number	Celestial GST			Property State/Country	TX / US
Project Name	CIP - Water Storage Facilities				

Photos



Photo 57	Perimeter Fence
Category: Safety & Security	



Photo 58	Gate
Category: Safety & Security	



APPENDIX D

Preliminary Design Report – Structural Condition Assessment

CONDITION ASSESSMENT REPORT

Celestial Ground Storage Tank Addison, Texas

Date: May 5, 2014

Size: 6 Million Gallon

Type: Concrete Ground Storage

Diameter: 206 Feet

Height: 25 Feet

Manufacturer: Preload Co., Inc.

Construction: 1986



GENERAL

Nathan D. Maier Consulting Engineers, Inc. (NDM) was retained by Kleinfelder Inc. (KLF) to assist in the evaluation of the structural integrity of the Celestial Ground Storage Tank located at 5510 Celestial Road. This condition assessment report (CAR) addresses the findings from the visual observation of this structure performed on January 27th, 2014, and provides general recommendations for maintenance, repair, and/or rehabilitation specific to the observations of the interior and exterior of the structure. The tank was full (approximately at overflow elevation) of water during the evaluation. The structural evaluation of the interior was performed by floating the tank in an inflatable raft. Underwater observations were performed by others during diving operations. NDM personnel were in contact with the divers and have reviewed the information provided from the



underwater review. Evaluation of the exterior was performed by visual observation. Working drawings from original construction were provided for review in conjunction with evaluation of the tank.



Exterior Site View

A. General Description:

The Celestial tank is a 6 Million Gallon concrete-constructed ground storage tank. The foundation consists of a slab-on-grade concrete footing over a compacted aggregate subgrade. The walls of the tank consist of composite precast concrete wall panels finished with pneumatic mortar. The base of the walls also consist of encased prestressed galvanized cables. The roof structure consists of a seven and a half-inch (7½-in.) reinforced concrete flat slab supported by an interior column grid consisting of sixty-nine (69) columns. The columns are sixteen inches (16 in.) in diameter and include three and a half foot (3.5 ft.) rectangular concrete capitals at the top (1.08 ft. deep) and rectangular concrete bases at the bottom. The concrete bases are four feet by four feet (4.0 ft. x 4.0 ft.). The roof hatch is a Bilco hatch and the ladder access for the interior of the tank is caged. There is a single vent located near the eastern edge of the roof. The inlet piping on the roof is supported by one concrete pipe support. The tank location slopes in grade from the north to the south exposing an additional ten to twelve feet of the tank on the lower side. Minor erosion was noted along the base of the tank in the lower areas. Various shrubs and bushes are present around the foundation in some areas, but



Exterior Site View -Opposite



Interior Roof Structure and Columns



Typical Column Base

much of the vegetation has died. Evidence of an irrigation system was present around the foundation of the tank. It was not clear if the irrigation system was operational.

B. General Observations:

The exterior of the tank around the foundation appears to be in good condition. There are no visible signs of foundation movement. There appears to be adequate drainage around the tank foundation away from the structure and the overflow flume extends adequately away from the tank. The exterior tank walls also appear to be in good condition. Cracking is visible in the outer coating surrounding the entire tank structure but these cracks do not appear to be significant at this time and there are no signs of seepage or moisture.

The exterior roof is basically flat and does not drain well. There is evidence of ponding water in several locations. Cracking in the roof slab was also noted from both the exterior and interior surfaces.

The interior of the tank is generally in good condition. No concerns were identified in the columns. The wall panels were in good condition. Cracking was observed in the structure floor. There was some deterioration observed at the joint along the tops of the wall panels.

The interior roof structure is generally in good condition. However, throughout the entire roof of the structure, there is evidence of the reinforcing steel chairs corroding and beginning to penetrate the surface of the concrete. It appears that the chairs may not have had plastic tips when installed. There was some evidence of minor cracking in the roof, but no concerns regarding cracking were identified. Corrosion was observed on the sonic level transmitter interior piping.




Exterior Wall Cracking



Ponding and Cracking in Exterior Roof



Interior Roof Cracking



Corrosion of Steel Overflow Structure



Corrosion of Bolts on Overflow Piping

Interior fill and discharge piping appeared to be in generally good condition. The two steel overflow structures showed signs of significant corrosion. The interior of the vent structure appeared functional and was in good condition. The interior ladder cage is in generally good condition.

These observations address only structural elements for the integrity of the tank. Safety, access, code compliance, coatings, etc., are addressed in KLF's section of this report.

C. Recommendations:

1. **Exterior Site Landscaping:** Consider addressing vegetation to control erosion around the foundation of the tank.
2. **Walls (Exterior):** Continue to monitor cracking. If cracks become more significant or begin to show signs of moisture, they will need to be addressed.
3. **Roof (Exterior):** Continue to monitor cracking. If cracks become more significant they will need to be addressed.
4. **Roof (Interior):** Continue to monitor the spalled areas and exposed reinforcing areas. The next time the tank is taken out of service, these areas should be repaired. At a minimum, these areas should be reviewed annually to monitor progression. If the tank is not taken out of service for some time, it is likely it will then need to be taken out of service to specifically repair these areas. Depending on the extent of the corrosion at that time, the areas may repeatedly spall even after initial repair and subsequent repairs will be necessary and therefore, should be included as a long term maintenance item.
5. **Floor (Interior):** Cracking in the structure floor should be sealed.



Typical Wall Panel Joint



Interior Access Ladder



Interior Piping



Crack in Tank Floor



6. **Overflow Structure and Piping (Interior):** The next time the tank is taken out of service, the corroded upper portion of the structure should be replaced and corroded bolts should be removed and replaced.

7. **Sonic Level Transmitter (Interior):** The next time the tank is taken out of service, the corroded portion of the piping should be prepared and recoated.

8. **Regular Structural Assessment:** It is recommended that a program is implemented that includes a scheduled structural evaluation to specifically monitor and evaluate the structural performance of the tank over time.

D. Opinion of Conceptual Anticipated Repair Costs:

Exterior Site Landscaping (Removal and Mitigation):	\$7,500.00
Walls (Exterior): (Monitor Only)	\$0.00
Roof (Exterior): (Monitor Only)	\$0.00
Roof (Interior): (Assumes 400 SF Spalling Repair)	\$20,000.00
Floor Interior: (Assumes 200LF Crack Sealing)	\$5,400.00
Overflow Structure and Piping: (Interior) (See KLF Section for Coatings)	\$5,000.00
Sonic Level Transmitter Piping (Interior) (See KLF Section for Coatings)	\$0.00
30% Contingency	\$8,370.00
Structural Repair Total:	\$46,270.00
Alternate Cost to Structurally Enhance Roof Structure if Required: (Assumes 1,750 SF FRP)	\$87,500.00




This cost is inclusive of the items discussed above and only includes elements for structural rehabilitation and maintenance.



APPENDIX E


Summary of Ratings for Physical Condition, Performance and Rules

Structural Assessment - Physical Condition




	Roof	Columns(s)	Grout/Caulk	Shell (Wall)	Floor
■ Rating (1 - Excellent, 2 - Good, 3 - Moderate, 4 - Poor, 5 - Critical)	3	2	4	2	2

Structural Assessment - Performance




	Roof	Columns(s)	Grout/Caulk	Shell (Wall)	Floor
■ Performance (1 - Excellent, 2 - Good, 3 - Moderate, 4 - Poor, 5 - Critical)	3	2	3	2	2

Structural Assessment - Rule




	Roof	Grout/Caulk	Floor
■ Rule (1 - Exceeds, 2 - Acceptable, 3 - Needs Improvement)	1	3	2

Operational Assessment - Physical Condition




	Inlet Pipe	Outlet Pipe	Overflow Pipe	Vents
■ Rating (1 - Excellent, 2 - Good, 3 - Moderate, 4 - Poor, 5 - Critical)	2	2	2	2

Operational Assessment - Performance




	Inlet Pipe	Outlet Pipe	Overflow Pipe	Vents
■ Performance (1 - Excellent, 2 - Good, 3 - Moderate, 4 - Poor, 5 - Critical)	2	2	2	2

Operational Assessment - Rule




	Overflow Pipe	Vents
■ Rule (1 - Exceeds, 2 - Acceptable, 3 - Needs Improvement)	1	1

Safety & Security Assessment - Physical Condition




	Roof Hatch	Ladder	Fencing & Gate
■ Rating (1 - Excellent, 2 - Good, 3 - Moderate, 4 - Poor, 5 - Critical)	2	2	2

Safety & Security Assessment - Performance




	Roof Hatch	Ladder	Fencing & Gate
■ Performance (1 - Excellent, 2 - Good, 3 - Moderate, 4 - Poor, 5 - Critical)	2	2	2

Safety & Security Assessment - Rule




	Roof Hatch	Tie-off Point	Ladder	Fencing & Security
■ Rule (1 - Exceeds, 2 - Acceptable, 3 - Needs Improvement)	1	3	1	1

Coating Assessment - Physical Condition



	Exterior Coating
■ Rating (1 - Excellent, 2 - Good, 3 - Moderate, 4 - Poor, 5 - Critical)	2

Coating Assessment - Performance



■ Performance (1 - Excellent, 2 - Good, 3 - Moderate, 4 - Poor, 5 - Critical)	Exterior Coating
	1