RESOLUTION NO.	
----------------	--

A RESOLUTION OF THE CITY COUNCIL OF THE TOWN OF ADDISON, APPROVING THE PURCHASE OF CERTAIN HVAC EQUIPMENT FOR VARIOUS TOWN FACILITIES FROM TEXAS AIR SYSTEMS IN CONNECTION WITH THE TOWN'S REQUEST FOR PROPOSALS 22-02 ENTITLED "RFP 22-02 HVAC AND GUN RANGE FACILITY UPGRADGES PROJECT"; AUTHORIZING THE CITY MANAGER TO EXECUTE THE PURCHASE DOCUMENTS; AND PROVIDING AN EFFECTIVE DATE.

WHEREAS, the City Council desires to authorize the purchase of certain HVAC equipment from Texas Air Systems described in the Quotation from Texas Air Systems dated 11/4/2021 and attached hereto as **Exhibit A** (the "Quote").

NOW, THEREFORE, BE IT RESOLVED BY THE CITY COUNCIL OF THE TOWN OF ADDISON, TEXAS:

<u>SECTION 1</u>. The City Council hereby approves a purchase between the Town of Addisonand Texas Air Systems for that certain HVAC equipment highlighted in green and described in the Quote dated 11/4/2021 in an amount not-to-exceed of \$511,056, a copy of which is attached this Resolution as <u>Exhibit A</u>. The foregoing HVAC equipment shall be used in connection withthe HVAC and Gun Range Facility Upgrades Project and City Manager is hereby authorized to execute such purchase orders and other documents as may be necessary to effectuate the purchase and delivery of the same.

SECTION 2. This Resolution shall take effect from and after its date of adoption.

DULY RESOLVED AND ADOPTED by the City Council of the Town of Addison, Texas, on this the 9^{th} day of **NOVEMBER** 2021.

	TOWN OF ADDISON, TEXA		
	Joe Chow, Mayor		
	ATTEST:		
Irma Parker, City Secretary	_		

EXHIBIT A

QUOTATION

Date: 11/04/2021

To: McKinstry / Town of Addison By: Cody Mason/Sean Moore

Project: Town of Addison Engineer: MEPCE

Based on Plans Dated: 09/21/2021



Note: Texas AirSystems is a member of the TIPS purchasing program.

If the equipment for all of the buildings included in this quote is purchased from Texas AirSystems, Texas AirSystems will offer a deduct of \$20,000 from the total price of this job. This discount will make the total price \$511,056.

Pricing Summary: Events Pavilion

DESCRIPTION	QTY	TAGGING	TOTAL NET PRICE
Champion Split System (Basis of Design)	4	AHU/CU-1 thru 4	\$18,784

^{*}FOB Factory, Full Freight Allowed, Tax Not Included

Bid Note: The pricing on this quote is only valid until December 20, 2021.

Champion Split System

Tags: AHU/CU-1,2,3,4

Four (4) *Champion* modular heat pump split systems designed for 208V/3ph/60Hz and complete as follows:

Outdoor Condensing Unit:

- Galvanized steel painted cabinet construction
- Two-step scroll compressor utilizing R-410A refrigerant
- 2-Stage
- Compressor Crank Case heater

Indoor Unit:

- Unit cabinet constructed of aluminum or G90 galvanized steel
- G30 Galvanized Steel Case to resist corrosion
- MaxAlloy Aluminum coils for long lasting performance, efficiency and reliability
- Insulated cabinet with foil faced insulation
- Thermal plastic drain pan
- Bolt-on-TXV
- Variable speed ECM Motor

Accessories:

- Electric heat kit *field mounted and wired by Others*
- 7-Day programmable thermostat *field mounted and wired by Others*
- Condensate overflow switch <u>field mounted and wired by Others</u>
- Dirty Filter Switch <u>field mounted and wired by Others</u>
- Disconnect switch <u>field mounted and wired by Others</u>
- MERV-13 Filter

TexasAirSystems.com

6029 Campus Circle Drive W., Suite 100, Irving, TX 75063 • Main: 972.570.4700 • Fax: 972.570.4207

Page 1 of 13

Warranties:

- 5 -Year limited parts warranty for indoor unit
- 10-Year Limited parts warranty for outdoor condensing unit

NOTES:

- 1. Unloading, rigging, installation, wiring, <u>STARTUP</u>, & refrigerant piping are not included and are by others.
- 2. The above pricing does not include housekeeping pads, low ambient controls, interconnecting piping, secondary drain pans, sensors, BAS/EMS controls, or smoke detectors.

Pricing Summary: Pump Station (Base Bid)

DESCRIPTION	QTY	TAGGING	TOTAL NET PRICE
Loren Cook Exhaust Fans (Basis of Design)	2	EF-1 & 2	Included
ABB Variable Frequency Drive	1	For EF-1	Included
Price Industries Air Devices (Basis of Design)	2	E1	Included
TOTAL NET PRICE			\$7,844

^{*}FOB Factory, Full Freight Allowed, Tax Not Included

Bid Note: The pricing on this quote is only valid until December 20, 2021.

Loren Cook Roof Mounted Hooded Exhaust Ventilators

Tags: EF-1

Loren Cook Model HEE, low profile, direct driven, hooded exhaust ventilator designed for 460V/3Ph/60HZ power and complete with the following:

- Bolted and welded construction
- Painted, welded steel fan housing with integral spun venturi and welded curb cap / 14 gauge
- Bolted fan housing hood with removable top cap
- Steel fan components have Lorenized baked powder finish
- Extruded aluminum propeller
- Direct Drive Premium Efficiency ODP motor with <u>shaft grounding ring</u> suitable for VFD control *See VFD scope later*
- L50 life in excess of 200,000 hours regreasable bearings
- Galvanized birdscreen
- NEMA-3 toggle disconnect switch <u>Factory mounted & wired</u>
- Gravity backdraft damper
- Lifting Lugs Shipped loose for field installation by Mechanical Contractor

Not Included: Curb or curb adapter, DDC controls, thermostats, wall switches, external isolators, installation and/or wiring.

Cook Roof Mounted Exhaust Fans

Tags: EF-2

Loren Cook Model ACED roof mounted direct drive down-blast exhaust fans designed for 120V/1Ph/60Hz power and complete with the following:

- All aluminum housing
- Removable top cap with stainless steel quick release latches
- Birdscreen
- Non-overloading, backward inclined, aluminum wheel
- ODP motor

TexasAirSystems.com

6029 Campus Circle Drive W., Suite 100, Irving, TX 75063 • Main: 972.570.4700 • Fax: 972.570.4207

Page 2 of 13

- Variable speed controller Factory mounted and wired
- Non fused disconnect switch Factory mounted and wired
- Gravity backdraft damper

Not Included: <u>Curb or curb adapter, Interlocks</u>, installation, wiring, startup, auxiliary motor starters, or controls not mentioned above.

ABB Variable Frequency Drives

Tags: For EF-1

ABB Model ACH580 variable frequency drives designed for 208V/3Ph/60HZ & 460V/3Ph/60HZ power and complete as follows:

- Microprocessor based Pulse Width Modulated (PWM) adjustable speed AC drive
- IGBT power switching technology
- NEMA-1 rated enclosure For indoor mounting and use only
- Full graphic multifunction control panel with LCD display in plain English
- Operating range from -10 to 40°C
- (2) programmable analog inputs / (2) programmable analog outputs
- (6) programmable digital inputs / (3) programmable relay outputs
- 5% input line impedance for harmonic mitigation
- Integral disconnect
- Integral Johnson Controls N2, Siemens FLN, Modbus & BACnet protocol
- 24- month parts and labor warranty with start-up from Texas AirSystems
- Factory Start-Up by Texas AirSystems

Not Included: Installation and wiring.

Price Industries Air Devices

Tags: E1

Grilles, registers, and diffusers per air device schedule, including:

- White powder coat finish
- Integral OBD Tag S1 for Stone Cottage
- Aluminum construction
- Insulated backpan Tag S1 & R1 for Gun Range

Excludes remote cable dampers, face operable dampers (unless noted), sheet metal fittings, spin-in taps, manual volume dampers, or other accessories not listed as included above.

Pricing Summary: Fire Station 2

DESCRIPTION	QTY	TAGGING	TOTAL NET PRICE
AAON Packaged DX Rooftop Units (Basis of Design)	3	RTU-1,2,3	Included
Space Ray Radiant Heaters (Basis of Design)	2	RH-1 & 2	Included
TOTAL NET PRICE			\$67,362

^{*}FOB Factory, Full Freight Allowed, Tax Not Included

Bid Note: The pricing on this quote is only valid until December 20, 2021.

AAON Packaged DX Rooftop Units

Tag: RTU-1,2,3

Three (3) AAON Models RN and RQ, roof mounted, air-cooled, vertical airflow, electric cooling, gas heating, packaged Rooftop unit, designed for 208V/3Ph/60HZ power, and complete as follows:

• R-410A refrigerant

TexasAirSystems.com

6029 Campus Circle Drive W., Suite 100, Irving, TX 75063 • Main: 972.570.4700 • Fax: 972.570.4207

Page 3 of 13

- Double wall, 2" thick, galvanized steel construction with gray polyurethane finish, R-13 foam insulation
- Sloped stainless steel drain pans
- · Access doors with full length stainless steel piano hinges and quarter turn, zinc cast lockable handles
- Enthalpy based Economizer
- Digital scroll compressor (lead circuit) mounted on RIS isolators per schedule
- Filter section with 2" thick, MERV 8 pre-filters with 4" thick MERV 13 filters two (2) sets per RTU per schedule
- · Direct drive backward curved plenum blowers with rubber isolation mounts and integral VFD
- Condenser section with VFD or EC motor on fans

Options and Accessories Included:

- 2-stage aluminized Heat Exchanger
- Modulating hot gas reheat
- Disconnect Switch factory mounted & wired
- Non-Powered Convenience outlet <u>factory mounted & wired</u>
- Condensate Overflow Switch <u>factory mounted & wired</u>
- Condenser Coil Guards factory mounted
- 7-Day Programmable Thermostat <u>field installed by Others</u>

Controls:

o AAON Single-Zone VAV Unit Mounted Controller for SZVAV Cooling and CV Heating

Services and Warranties:

- Standard one-year warranty on all parts
- 5-year non-prorated compressor warranty (parts only)
- 25-year non-prorated Stainless-Steel Heat Exchanger Warranty
- Start-up of RTU by AAON technician

Coordination Notes:

- Roof curb or curb adapters are not included.
- Labor warranty is not included and is to be carried by others.
- Controls, wiring, rigging, i1nstallation are not included.
- Smoke Detectors, Secondary GFI Outlets, Clogged Filter Switches are not included

Space-Ray Infrared Radiant Gas Heaters

Tags: RH-1 & 2

Space-Ray model PTS tubular infrared heater designed for 120V/1Ph/60Hz and complete with the following:

- Totally enclosed combustion chamber
- Blower motor totally enclosed in the burner box
- Heavy duty cast iron burner
- Direct spark ignition system and 100% gas shut off safety control
- Pre-purge and post-purge functions
- Diaphragm air switch for proof of venting before gas flow ignition
- Tube Integrity Safety System
- Highly efficient aluminum reflectors
- Chain kit
- 2-stage thermostat 24V Field installed & wired by others
- Gas flex connectors
- 10-year limited warranty on burner

Not Included: Installation, wiring, startup, or controls not mentioned above.

TexasAirSystems.com

6029 Campus Circle Drive W., Suite 100, Irving, TX 75063 • Main: 972.570.4700 • Fax: 972.570.4207

Page 4 of 13

Pricing Summary: Stone Cottage

DESCRIPTION	QTY	TAGGING	TOTAL NET PRICE
Champion Split Systems (Basis of Design)	2	AHU/CU-1,2	Included
Loren Cook Exhaust Fan <i>(Basis of Design)</i>	1	EF-1	Included
Price Industries Air Devices (Basis of Design)	6	S1	Included
TOTAL NET I	\$19,466		

^{*}FOB Factory, Full Freight Allowed, Tax Not Included

Bid Note: The pricing on this quote is only valid until December 20, 2021.

Champion Split System

Tags: AHU/CU-1,2

One (1) *Champion* modular direct expansion split systems designed for 230V/1ph/60Hz and complete as follows:

Outdoor Condensing Unit:

- Galvanized steel painted cabinet construction
- Two-step scroll compressor utilizing R-410A refrigerant
- Compressor Crank Case heater

Indoor Unit:

- Unit cabinet constructed of aluminum or G90 galvanized steel
- G30 Galvanized Steel Case to resist corrosion
- · MaxAlloy Aluminum coils for long lasting performance, efficiency and reliability
- Insulated cabinet with foil faced insulation
- Thermal plastic drain pan
- Bolt-on-TXV
- Variable speed ECM Motor

Accessories:

- Electric heat kit *field mounted and wired by Others*
- 7-Day programmable thermostat *field mounted and wired by Others*
- Condensate overflow switch <u>field mounted and wired by Others</u>
- Dirty Filter Switch <u>field mounted and wired by Others</u>
- Disconnect switch <u>field mounted and wired by Others</u>
- MERV-13 Filter

Warranties:

- 5 -Year limited parts warranty for indoor unit
- 10-Year Limited parts warranty for outdoor condensing unit

NOTES:

- Unloading, rigging, installation, wiring, <u>STARTUP</u>, & refrigerant piping are not included and are by others.
- 4. Condensing units come with enough refrigerant for matching evaporator coils and 15 feet of interconnecting piping Additional required refrigerant is not included and is by others.
- 5. The above pricing does not include housekeeping pads, <u>low ambient controls</u>, interconnecting piping, secondary drain pans, sensors, BAS/EMS controls, smoke detectors, or disconnect switches.

Cook Ceiling Exhaust Fans

Tags: EF-1

Loren Cook Model GC ceiling mounted exhaust fans designed for 120V/1Ph/60Hz power and complete as follows:

• Injection molded flame resistant fan housing

TexasAirSystems.com

6029 Campus Circle Drive W., Suite 100, Irving, TX 75063 • Main: 972.570.4700 • Fax: 972.570.4207

Page 5 of 13

- Galvanized steel inlet box
- Forward curved polypropylene fan wheel
- Round outlet duct with integral backdraft damper
- EC motor
- Plug-style disconnect
- White intake grille
- Isolator kit All-Thread rod by Others

Not Included: interlocks, light switches, installation, wiring, startup, transformers, roof or wall caps, flex connections, or controls not mentioned above.

Price Industries Air Devices

Tags: S1

Grilles, registers, and diffusers per air device schedule, including:

- White powder coat finish
- Integral OBD Tag S1 for Stone Cottage, Tag S3 for Gun Range
- Aluminum construction
- Insulated backpan Tag S1 & R1 for Gun Range

Excludes remote cable dampers, face operable dampers (unless noted), sheet metal fittings, spin-in taps, manual volume dampers, or other accessories not listed as included above.

Pricing Summary: Service Center

DESCRIPTION	QTY	TAGGING	TOTAL NET PRICE
JCI Packaged DX Rooftop Units (Basis of Design)	9	RTU-1 thru 9	Included
Champion Split System (Basis of Design)	1	FCU/CU-1	Included
LG Ductless Mini Split Systems (Basis of Design)	3	FCU/CU-DS-2,3,4	Included
Modine Gas Unit Heaters (Basis of Design)	10	UH-1 thru 10	Included
TOTAL NET PRI	CE		\$171,394

^{*}FOB Factory, Full Freight Allowed, Tax Not Included

Bid Note: The pricing on this quote is only valid until December 20, 2021.

JCI Packaged DX Rooftop Unit

Tag: RTU-1 thru 9

Nine (9) *Johnson Controls* packaged rooftop units designed for 460V/3Ph/60Hz and complete as follows:

- R-410A refrigerant
- 0-100%, low leak, economizer
 - o Single enthalpy kit field installed by Others
- 4" MERV-13 Filters Two (2) sets per schedule
- Direct expansion cooling coil with copper tube, aluminum finned cooling coil
- One-stage electric heat exchangers
- Belt drive, single-width, single inlet forward curved centrifugal supply fan
 - Single speed, ODP supply fan motors
- Hinged access doors
- Condenser coil hail guards <u>field installed by Others</u>
- Standard composite drain pans
- Disconnect switch <u>field wired by Others</u>
- 115V Non-powered convenience outlet <u>field wired by Others</u>

TexasAirSystems.com

6029 Campus Circle Drive W., Suite 100, Irving, TX 75063 • Main: 972.570.4700 • Fax: 972.570.4207

Page 6 of 13

- BACnet MS/TP communication interface
- One (1) year parts only warranty
- Five (5) year parts only compressor and electric heater elements warranty
- Ten (10) year parts only aluminized steel tubular heat exchanger warranty

Not Included: Installation, STARTUP, roof curb or curb adapter, thru the base condensate and gas connections, disconnect switches, smoke detectors, owner training, controls, double wall construction, condensate overflow switch, smoke detectors, thermostat, hot gas reheat, dirty filter switch, fault detection diagnostics, piping, low ambient kit, wiring and any controls not listed above.

Champion Split System

Tags: FCU/CU-1

One (1) *Champion* modular direct expansion split systems designed for 230V/1ph/60Hz and complete as follows:

Outdoor Condensing Unit:

- Galvanized steel painted cabinet construction
- Two-step scroll compressor utilizing R-410A refrigerant
- Compressor Crank Case heater

Indoor Unit:

- Unit cabinet constructed of aluminum or G90 galvanized steel
- G30 Galvanized Steel Case to resist corrosion
- MaxAlloy Aluminum coils for long lasting performance, efficiency and reliability
- · Insulated cabinet with foil faced insulation
- Thermal plastic drain pan
- Bolt-on-TXV
- Variable speed ECM Motor

Accessories:

- Electric heat kit *field mounted and wired by Others*
- 7-Day programmable thermostat *field mounted and wired by Others*
- Condensate overflow switch <u>field mounted and wired by Others</u>
- Dirty Filter Switch <u>field mounted and wired by Others</u>
- Disconnect switch <u>field mounted and wired by Others</u>
- MERV-13 Filter

Warranties:

- 5 -Year limited parts warranty for indoor unit
- 10-Year Limited parts warranty for outdoor condensing unit

NOTES:

- 6. Unloading, rigging, installation, wiring, <u>STARTUP</u>, & refrigerant piping are not included and are by others.
- 7. Condensing units come with enough refrigerant for matching evaporator coils and 15 feet of interconnecting piping Additional required refrigerant is not included and is by others.
- 8. The above pricing does not include housekeeping pads, low ambient controls, interconnecting piping, secondary drain pans, sensors, BAS/EMS controls, or smoke detectors.

TexasAirSystems.com

6029 Campus Circle Drive W., Suite 100, Irving, TX 75063 • Main: 972.570.4700 • Fax: 972.570.4207

Page 7 of 13

LG Ductless Split Systems

Tag: FCU/CU-2,3,4

Three (3) LG Model LS high efficient, ductless heat pump split systems, designed for 208V/1Ph/60HZ power and complete as follows:

- Cooling & Heating Heat Pump System / Duct free / Single Zone
- Inverter compressor utilizing R-410A refrigerant
- Variable speed compressor
- Low ambient operation to 14°F Cooling / -4°F Heating
- DX Coil with Gold FinTM Anti-corrosion
- Ultra-quiet fan
- Evaporator frost control
- 3M Micro Protection Filter
- Dip switch for inverter control & lockout for cooling/heating only applications
- Auto restart / Auto Changeover / 24-Hour on/off timer
- Programmable wall mounted thermostat <u>field installed by Others</u>
- Condensate pump <u>field installed by Others</u>
- Condensing unit rails field installed by Others
- Hail guards <u>field installed by Others</u>
- Standard 5-year Parts & 7-Year Compressor Warranties (Labor is not Included)

Not Included: Installation, rigging, wiring, STARTUP, motor starters, wind baffles, disconnects, low ambient kits, mounting pads, refrigerant line sets, BMS/BAS integration, or controls not mentioned.

Modine Gas Fired Unit Heater

Tag: UH-1 thru 10

Modine Model HD gas fired unit heatet designed for 115V/1Ph/60Hz and complete with the following:

- 60MBH
- Heavy gauge metal casing
- Direct spark ignition
- Factory installed finger proof fan guards
- Permanently lubricated motor
- ½" gas connection
- Ceiling mounting kit
- Thermostat Field installed & wired by others
- 10-year heat exchanger warranty

NOT INCLUDED: Disconnect (by Div. 26 per schedule), roof caps, installation, wiring, STARTUP, flue pipe

Pricing Summary: Gun Range

inemg cummuly, cum rumge			
DESCRIPTION	QTY	TAGGING	TOTAL NET PRICE
AAON Packaged DX Rooftop Unit (Basis of Design)	1	RTU-1	Included
JCI Packaged DX Rooftop Unit (Basis of Design)	1	RTU-2	Included
RVD Range Ventilation Control Panel (Basis of Design)	-	As detailed & noted	Included
RVD Laminar Airflow Radial Diffusers (<i>Basis of Design</i>)	6	S2	included
Aire-Loc 3-Stage Filter Rack (Basis of Design)	2	As detailed & noted	Included
Loren Cook Exhaust Fan <i>(Basis of Design)</i>	2	EF-1, RF-1	Included

TexasAirSystems.com

6029 Campus Circle Drive W., Suite 100, Irving, TX 75063 • Main: 972.570.4700 • Fax: 972.570.4207

Page 8 of 13

ABB Variable Frequency Drive	2	For EF-1 & RF-1	
Redd-I Electric Unit Heater (Basis of Design)	1	UH-1	Included
Price Industries Air Devices	14	S1, S3, R1	Included
TOTAL NET PRICE			\$246,206

^{*}FOB Factory, Full Freight Allowed, Tax Not Included

Bid Note: The pricing on this quote is only valid until December 20, 2021.

AAON Packaged DX Rooftop Units

Tag: RTU-1

One (1) **AAON** Models RN, roof mounted, air-cooled, vertical airflow, electric cooling, electric heating, packaged Rooftop unit, designed for 208V/3Ph/60HZ power, and complete as follows:

- R-410A refrigerant
- Double wall, 2" thick, galvanized steel construction with gray polyurethane finish, R-13 foam insulation
- Sloped stainless steel drain pans per schedule
- · Access doors with full length stainless steel piano hinges and quarter turn, zinc cast lockable handles
- 4-Stage electric heat
- Enthalpy based Economizer with powered return
- Digital scroll compressor (lead circuit) mounted on RIS isolators as scheduled
- Filter section with 2" thick, MERV 8 pre-filters with 4"thick MERV 13 filters two (2) sets per RTU per schedule
- Direct drive backward curved plenum blowers with rubber isolation mounts and integral VFD
- Condenser section with VFD or EC motor on fans

Options and Accessories Included:

- Condenser Coil Guards
- 4 stage electric Heat Exchanger
- Modulating hot gas reheat per schedule
- Non-Powered Convenience outlet <u>factory mounted & wired</u>
- Condensate Overflow Switch <u>factory mounted & wired</u>
- Outside airflow measuring station <u>factory mounted & wired</u>

Controls:

AAON Constant Volume Unit Controller

Roof Curbs:

• 14" high, insulated, galvanized steel roof curbs for flat, built up, roof - field installed by Others

Services and Warranties:

- Standard one-year warranty on all parts
- 5-year non-prorated compressor warranty (parts only)
- 25-year non-prorated Heat Exchanger Warranty
- Start-up of RTU by AAON technician

Coordination Notes:

- Labor warranty is not included and is to be carried by others.
- · Controls, wiring, rigging, i1nstallation are not included.
- Smoke Detectors, return airflow measuring station, disconnects, Secondary GFI Outlets, Clogged Filter Switches are not included

JCI Packaged DX Rooftop Unit

Tag: RTU-2

One (1) Johnson Controls packaged rooftop units designed for 208V/3Ph/60Hz and complete as follows:

- R-410A refrigerant
- 0-100%, low leak, economizer

TexasAirSystems.com

6029 Campus Circle Drive W., Suite 100, Irving, TX 75063 • Main: 972.570.4700 • Fax: 972.570.4207

Page 9 of 13

- Single enthalpy kit <u>field installed by Others</u>
- 4" MERV-13 Filters Two (2) sets per schedule
- · Direct expansion cooling coil with copper tube, aluminum finned cooling coil
- One-stage electric heat exchangers
- Belt drive, single-width, single inlet forward curved centrifugal supply fan
 - o Single speed, ODP supply fan motors
- Hinged access doors **per schedule**
- Condenser coil hail guards <u>field installed by Others</u>
- Standard composite drain pans
- 115V Non-powered convenience outlet <u>field wired by Others</u>
- BACnet MS/TP communication interface
- 14" high, insulated, galvanized steel roof curb for flat, built up, roof <u>field installed by others</u>
- One (1) year parts only warranty
- Five (5) year parts only compressor and electric heater elements warranty
- Ten (10) year parts only aluminized steel tubular heat exchanger warranty

Not Included: Installation, <u>STARTUP</u>, <u>condensate overflow switch</u>, <u>disconnect switches</u>, smoke detectors, owner training, <u>thru the base condensate and gas connections</u>, controls, double wall construction, <u>smoke detectors</u>, thermostat, hot gas reheat, dirty filter switch, fault detection diagnostics, piping, low ambient kit, wiring and any controls not listed above.

Range Ventilation Design (RVD) Gun Range System

Tags: As noted and detailed

The RVD gun range system shall be complete as follows:

- Range ventilation control pane model RVC-5000-R-R-HCF-R
 - Installation included
 - o Control wiring & terminations included
 - Carbon monoxide monitor included
 - System commissioning included
- Qty. (6) Laminar Airflow Radial diffusers model RD-2400

Field installed by others

o Certification for laminar airflow by RVD

NOT INCLUDED:

- 1. Installation of radial diffusers
- 2. Airflow measuring stations
- 3. Continuous RVD presence on-site
- 4. Smoke detectors
 - a. RVD panel has capability to shut down all fans if a dry contact closure is brought back to RVD control panel. Dry contact closure is NOT included and to be field installed & wired by others.
- 5. Permits, duties, and other fees are not included.
- 6. Installation, wiring, additional controls, vibration isolation, all-thread rod

Aire-Loc 3-Stage Filtration System

Tags: As noted and detailed

The 3-stage gun range filtration system shall be complete as follows:

- 14ga galvanized steel outer casing
- Weatherproof construction
- Housing rated for +/- 10" W.C.
- Door perimeter sealed with closed cell neoprene gasketing
- Access doors fitted with knurl knob bolt down latches and uni-hinges
- Housing #1 associated with EF-1

TexasAirSystems.com

6029 Campus Circle Drive W., Suite 100, Irving, TX 75063 • Main: 972.570.4700 • Fax: 972.570.4207

Page 10 of 13

- o 50"x60"x27.5" (WxLxH)
- O Qty. (2) 24x24x4 MERV8 Pre-Filters
- o Qty. (2) 24x24x30 MERV15 Bag Filter
- o Qty. (2) 24x24x12 HEPA Filter
- Housing #2 associated with RF-1
 - o 74"x60"x52" (WxLxH)
 - o Qty. (6) 24x24x4 MERV8 Pre-Filters
 - o Qty. (6) 24x24x30 MERV15 Bag Filter
 - O Qty. (6) 24x24x12 HEPA Filter

Coordination Note: Only Qty. (1) set of filters is included in the base bid. ADD is presented for additional sets of filters if desired.

Loren Cook Roof Mounted Industrial Material Handlers

Tags: EF-1

Loren Cook Model MHA, roof mounted, SWSI, backward inclined flat blade, belt driven, exhaust designed for 208V/3Ph/60Hz power and complete with the following:

- Bolted and continuously welded leakproof steel construction utilizing corrosion resistant fasteners
- Rigidly reinforced housing side panels to prevent flexing and vibration
- Steel fan components have Lorenized baked powder finish
- Centrifugal backward inclined steel fan
- Premium Efficiency ODP motor suitable for VFD control *See VFD scope later*
- Steel weather cover with access ports with quick release latches
- OSHA belt guard/weathercover
- L50 life in excess of 200,000 hours regreasable bearings
- Extended lube lines
- Isolation base with isolators
- Integral drain in fan housing
- Gravity shutter

Does NOT include <u>airflow CFM measurement</u>, DDC controls, thermostats, wall switches, installation and/or wiring.

Loren Cook Mixed Flow Blowers

Tags: RF-1

Loren Cook Model QMXD, tubular, direct driven, mixed flow inline blower designed for 208V/3Ph/60Hz power and complete with the following:

- Bolted construction 14 gauge galvanized steel
- Straightening vanes assure maximum efficiency and low noise
- Adjustable motor plate for positive belt tensioning
- Non-overloading, high efficiency aluminum mixed flow wheel
- Horizontal hanging brackets
- Direct Drive Premium Efficiency ODP motor with <u>shaft grounding ring</u> suitable for VFD control *See VFD scope later*
- Spring isolators all-thread rod by others

Notes: Does NOT include <u>airflow CFM measurement</u>, DDC controls, thermostats, wall switches, installation and/or wiring.

TexasAirSystems.com

6029 Campus Circle Drive W., Suite 100, Irving, TX 75063 • Main: 972.570.4700 • Fax: 972.570.4207

Page 11 of 13

ABB Variable Frequency Drives

Tags: For EF-1 & RF-1

ABB Model ACH580 variable frequency drives designed for 208V/3Ph/60HZ & 460V/3Ph/60HZ power and complete as follows:

- Microprocessor based Pulse Width Modulated (PWM) adjustable speed AC drive
- IGBT power switching technology
- NEMA-1 rated enclosure For indoor mounting and use only
- Full graphic multifunction control panel with LCD display in plain English
- Operating range from -10 to 40°C
- (2) programmable analog inputs / (2) programmable analog outputs
- (6) programmable digital inputs / (3) programmable relay outputs
- 5% input line impedance for harmonic mitigation
- Integral disconnect
- Integral Johnson Controls N2, Siemens FLN, Modbus & BACnet protocol
- 24- month parts and labor warranty with start-up from Texas AirSystems
- Factory Start-Up by Texas AirSystems

Not Included: Installation and wiring.

Redd-i Electric Plenum Heater

Tags: UH-1

Redd-i Model 7200 electric plenum heater designed for 208V/3Ph/60HZ and 277V/1Ph/60Hz power and complete as follows:

- 20ga galvanized cabinet
- Variable speed motor
- 1" fiberglass acoustical insulation
- Access panels on both sides of unit
- 24v controls with disconnect switch
- Air flow switch
- 0" clearance on sides, top and bottom
- Dust tight control enclosure
- Filter rack with throw away filter
- SCR modulating heat control
- Wall thermostat Field installed & wired by others

NOT INCLUDED: Installation, wiring, additional controls, vibration isolation, all-thread rod

Price Industries Air Devices

Tags: S1, S3, R1

Grilles, registers, and diffusers per air device schedule, including:

- White powder coat finish
- Integral OBD Tag S3 for Gun Range
- Aluminum construction
- Insulated backpan Tag S1 & R1 for Gun Range

Excludes remote cable dampers, face operable dampers (unless noted), sheet metal fittings, spin-in taps, manual volume dampers, or other accessories not listed as included above.

TexasAirSystems.com

6029 Campus Circle Drive W., Suite 100, Irving, TX 75063 • Main: 972.570.4700 • Fax: 972.570.4207

Page 12 of 13

-This quotation is subject to change without notice and void after 15 days.

-Add to the prices quoted any sales tax payable on the transaction under any effective Federal or State statute.

-F.O.B. Factory, FFA, per mutually agreed schedule. No material to be returned without written authorization.

-Payment terms: Net 30 Days, Upon Receipt of Satisfactory Credit Information.

-Texas AirGystems equipment will be supplied based upon approved submittal data.

-Retainage is not allowed. Texas AirGystems is a material supplier, and will be supplying the entire purchase order value upon delivery of equipment.

-Payment to Texas AirGystems cannot be conditioned on receipt of payment from the owner by a contractor, construction manager, or customer.

-Texas AirGystems standard warranty, parts only, is for 12 months from stating date, not to exceed 18 months from ship date.

- Texas AirGystems is responsible and accountable only for the acts and omissions of Texas AirGystems.

-Insurance certificates and bonds can/will be provided upon request.

TexasAirSystems.com

6029 Campus Circle Drive W., Suite 100, Irving, TX 75063 • Main: 972.570.4700 • Fax: 972.570.4207

Page 13 of 13